ADDENDUM

The specification of the code08 in the BOQ should be considered as follows”

CODE08 ” Spreading of stone dust: Supplying and providing stone dust in the station yard or whereever required including watering, ramming, consolidating and dressing. the rates includes the cost of the material, labour charges, required tools and plants etc, complete. work shall be carried as per instruction of engineering in charge of works as per standard procedure”

Sd/-

Tender inviting authority